

20' Modular Building Unit

STANDARD FEATURES

- IBC 2015 compliant for 150 mph wind & Seismic Zone D
- Stackable 3-high
- · Constructed Unit: 9' 6" High
- · (1) set of standard forklift pockets
- A60 Insulated wall panels: 4" supplied with integrated window panels (4 each) and door panel (1 each) are relocatable
- (1) External fire-rated door, 78.50" x 33.25" opening
- (4) Single hung windows, 53" x 34"
- (1) A/C opening, 16.25" x 26.00"
- · Electrical Components:
 - 220V Single Phase
 - (2) Overhead light fixtures
 - (3) Flush mounted 4-way receptacles
- (1) Motion sensor switch
- Telephone/Cable Components:
 (3) RJ45 receptacles
 (2) D 141 telephone recented
 - (3) RJ11 telephone receptacles
- Modules can be connected to create larger complexes in multi-story configurations
- Heating and Cooling Unit: 12,000/10,000 BTU (cool/heat)

OPTIONAL FEATURES

- · Connection Kits (create larger structures)
- · Stairs and Platforms
- · Furniture (desk, tables and chairs)







LENGTH HEIGHT WIDTH MANAGEMENT SYSTEM Tare Weight Exterior Interior Exterior Interior Exterior Interior 9' 6' 19' 0" 8' 0" 8' 0' 7'1" Ft in 19' 10 1/2' 5,700 lbs. 6.058 5.791 2.896 2,438 2,438 2.159 2,586 kg. Metric

ALL DIMENSIONS AND WEIGHTS ARE NOMINAL AND SUBJECT TO MINOR VARIATIONS THAT MAY OCCUR DURING THE MANUFACTURING PROCESS

Phone: 856 . 303 . 1101

Fax: 856 . 303 . 1501 | Email: sales@seabox.com

www.seabox.com

ISO 9001

